5. Persons bidding at the sale may be required to state whether they bid on their own account or as agents, and in the latter case to deposit a written authority signed by their principals, otherwise their bids may be rejected.

6. The sale shall be stayed, if the defaulter or any person acting on his behalf or claiming an interest in the property, tenders the full amount of the arrears of revenue with the interest and other charges, provided such tender be made before the property is knocked down to the highest bidder on the date of sale.

7. The sale of the property will not become absolute until confirmed by the Deputy Commissioner.

8. It is to be distinctly understood that the Government are not responsible for errors of description or in estimated extent.

9. Provided, parties deeming themselves aggrieved by the sale, shall be at liberty to appeal to the Deputy Commissioner within thirty days from the day of sale, and also to appeal to Government against his order within the time prescribed by law, and the purchase shall be conditional on the final order in such appeal.

SCHEDULE.

Taluk.	Hobli.	Village.	Names of defaulters.	Description of property.							Amount of arrears due to Government, including notice fees, etc.
				Buildings.		Land.					
				Name of building.	Estimated value.	Survey number or name of land.	Dry, wet or garden.	Area.	Assessment.		
								A. g.	Rs. a. p.		Rs. a. p.
Chiknagalur.	Mirle.	Hejjigenahalli.	Annegeri Shama Rao and Bhima Rao	...	...	...	Dry ...	105 37	107 5 7	Present arrears.	999 8 0
							Garden...	6 30	46 0 0	Processes fees	1 0 0
							Wet ...	70 4	427 15 11	Total ...	1,000 8 0
							Peramboke.	46 36	2 12 0	and also interest up to date of sale.	
							Total...	229 27	584 1 6		

PET. GEO. D'SOUZA, for *Dy. Comr.*

MYSORE PUBLIC WORKS DEPARTMENT.

(ELECTRICAL BRANCH.)

Bangalore Power and Lighting Scheme.

Dated 5th May 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chief Electrical Engineer to the Government of Mysore, up to 31st May 1904, for constructing three buildings in connection with Bangalore Power and Lighting Scheme, in Bangalore.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1904.

2. The plans, detailed estimate, and conditions may be seen at the Chief Electrical Engineer's Office at Bangalore, between the hours of 2 and 4 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Chief Electrical Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for Buildings in connection with Bangalore, Power and Lighting," in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. Competitors, whether successful or not, will be notified of the acceptance or otherwise of their tenders in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Detailed abstract estimate of constructing Buildings for Bangalore, Power and Lighting Works.

Items of work.	*Per.*	*Quantity.*
No. 1 Station to be located near Fort, Bangalore City—		
1. Earthwork, excavating and filling in basement	C. yd.	176
2. Concrete foundation	C. ft.	530
3. Stone in mortar	"	10269
4. Slab stones, 6" thick, roughly dressed	"	356
5. Brick archwork in cement	"	316
6. Stone ashlar work	"	189
7. Stone slabs, 6" thick, neatly dressed and chamfered ...	"	100
8. Cement pointing	Sqr.	86·13
9. Cement plastering	"	5·42
10. Mangalore tile flooring under 6" concrete	"	10·02
11. Mangalore tile roofing with ceiling tiles	"	19·68
12. Galvanized corrugated iron roofing	"	3·06
13. Teakwood work	"	218·00
14. Iron trusses 31 ft. clear span	Each	3
15. Carriage, hoisting and fixing charges for above ...	Lump sum.	
16. Iron trusses for lean-to roof	Each	3
17. Carriage, hoisting and fixing charges for above... ...	Lump sum.	
18. Teakwood doors	S.ft.	117
19. Teakwood windows	"	654
20. Circular ventilators	"	14
21. Ornamental finials	Each	2
22. Ornamental eave and barge boards 12" × 1"	R.ft.	178
23. Cast iron columns about 9' high	Each	5
24. Rolled iron beams including carriage	Cwt.	32·42
24a. Hoisting and fixing above	Lump sum.	
25. Cuddappah slab flooring 2" thick	Sqr.	4·37
26. Ornamental hand railing 3' high	R.ft.	60
27. Ornamental eave boards to gallery	"	65
28. Staircase 9' high and 2½' wide	Lump sum.	
29. Iron ladder about 10' long	Do	
30. Painting	Sqr.	50·00
No. 2 and 3 Stations.—One on the maidan near Mayo Hall, the other on St. John's Hill—		
(Approximate quantities for one building.)		
Earthwork	C.yd.	86
Concrete foundation	C.ft.	359
Stone in mortar	"	6018
Stone slabs, 6" thick, roughly dressed	S.ft.	202
Brick in cement archwork	C.ft.	279
Stone ashlar work	"	137
Stone slabs, 6" thick, neatly dressed and chamfered... ...	"	109
Cement pointing	Sqr.	56·80
Do plastering	"	4·50
Mangalore tile flooring over 6" concrete...	"	5·06
Do roofing with ceiling tiles, etc., complete ...	"	13·49
Teakwood work	C.ft.	150·43
Iron trusses 26' clear span	No.	2
Carriage, hoisting and fixing charges of above	Lump sum.	
Doors, teakwood	S.ft.	89
Windows, teakwood	"	553
Circular ventilators	"	14
Ornamental finials	No.	2
Ornamental eave and barge boards 12" × 1"	S.ft.	147
Cast iron columns about 9' high	No.	4
Rolled iron beams including casting, etc.	Cwt.	29·22
Hoisting and fixing above	Lump sum.	
Cuddappah slabs, flooring (2" thick)	Sqr.	3·52
Ornamental hand railing 3' high	S. ft.	43
Ornamental eave board to gallery	"	43
Staircase 2½' × 9'	Lump sum.	
Painting	Sqr.	30·00

H. P. GIBBS,
Chief Electrical Engineer to the Govt. of Mysore.